

# Digital Engineering – (BIM)

## Contractors Viewpoint

Andy Radley

03/10/2013

LAING O'ROURKE

Cannon Place, London, UK

# An engineering enterprise



LAING O'ROURKE



## Sectors and businesses

With a presence in all of the major building and infrastructure sectors, our internationally integrated delivery model serves clients in all phases of the project. We recognise that every project is unique and tailor our service offering to provide custom solutions to the highest standards of quality – on time and on budget.

Our sectors							
 <b>Business</b> <ul style="list-style-type: none"><li>• Commercial offices</li><li>• Data centres</li><li>• Industrial</li><li>• Science and research</li></ul>	 <b>Lifestyle</b> <ul style="list-style-type: none"><li>• Hotels</li><li>• Residential</li><li>• Retail</li><li>• Sport and leisure</li></ul>	 <b>Social infrastructure</b> <ul style="list-style-type: none"><li>• Defence</li><li>• Education</li><li>• Healthcare</li><li>• Law and order</li></ul>	 <b>Transport</b> <ul style="list-style-type: none"><li>• Aviation</li><li>• Highways</li><li>• Marine</li><li>• Rail</li></ul>	 <b>Power</b> <ul style="list-style-type: none"><li>• Generation</li><li>• Maintenance</li><li>• New nuclear</li><li>• Renewables</li></ul>	 <b>Utilities and waste</b> <ul style="list-style-type: none"><li>• Sewage</li><li>• Utility networks</li><li>• Waste</li><li>• Water treatment</li></ul>	 <b>Mining and natural resources</b> <ul style="list-style-type: none"><li>• Coal and mineral processing</li><li>• Labour accommodation</li><li>• Material transport</li><li>• Minerals handling</li></ul>	 <b>Oil and gas</b> <ul style="list-style-type: none"><li>• LNG terminals</li><li>• Pipelines and pump stations</li><li>• Processing plants</li><li>• Storage</li></ul>
Our businesses							
Investment and Development	 						
Manufacturing	        						
Construction and Building Services	 		Infrastructure Services		  		
Support Services	   						

## Vision and strategy

### Near term

#### Priorities

- Grow our talent
- Continue investment in health, safety and environment
- Manage our risks and achieve excellence in governance
- Deliver for clients and build long-term relationships
- Increase market share and improve our organisational fitness
- Maintain a lean and efficient cost base
- Drive DfMA through our core offering

### Medium term

#### Strategies

- Achieve Excellence Plus in our organisational capabilities
- Expand operations into complementary sectors and countries
- Generate sustainable returns over the long term, based on a vertically integrated delivery model

### Long term

#### Goals

- An exemplar employer
- Global blue-chip client base
- Core business of engineering and construction, plus selective professional services
- Diversified project portfolio of high-value sectors and attractive territories globally
- Operational and financial performance equivalent to sustaining an industry-leading position

### Vision and purpose

- We will be the company of first choice for all stakeholders
- We will challenge and change the image of construction worldwide
- With leanness and agility we will adopt processes to compete with world-leading businesses

**DfMA Strategy is to deliver  
70/60/30->0->0**

**DE is an enabler to DfMA**

**DfMA and DE are mandated  
within Laing O'Rourke on  
all new projects**

**70%** of the construction asset  
delivered via DfMA

**60%** labour reduction  
'on site'

**30%** programme reduction  
in areas we control

**Towards  
0%** carbon footprint

**Towards  
0%** AFR

Our stated DfMA objectives = your personal objectives








Digital Engineering

Work Winning and  
Post Win











### Frame

**Concrete frames** Definition: Concrete columns and beams.

**Sub element unit quantity: Concrete frames**

Total Concrete in columns, Reference measure

**Columns: details, including number (nr) of columns, column size (mm), concrete grade, reinforcement rate (kg/m<sup>3</sup>) and type of formwork finish, to be stated.**

Other columns - includes reinforcement @ 300kg/m<sup>3</sup>

**Walls: Details, including thickness of wall (mm), concrete grade, reinforcement rate (kg/m<sup>3</sup>) and type of formwork finish, to be stated.**

Concrete load bearing walls, 300mm thick

C50 concrete in 300mm walls

Formwork to 300mm walls

Reinforcement to 300mm walls 125kg/m<sup>3</sup>

Enhancement of finish to 300mm walls

Concrete non load bearing walls 200mm thick

C50 concrete in 200mm walls

Formwork to 200mm walls

Reinforcement to 200mm walls 100kg/m<sup>3</sup>

Enhancement of finish to 200mm walls

300mm x 350mm Upstands / Downstands generally to level perimeter including roof

Concrete load bearing walls, 300mm thick

C50 concrete in 300mm walls

Formwork to 300mm walls

Reinforcement to 300mm walls 125kg/m<sup>3</sup>

Enhancement of finish to 300mm walls

Concrete load bearing walls, 150mm thick

C50 concrete in 150mm walls

Formwork to 150mm walls

Reinforcement to 150mm walls 125kg/m<sup>3</sup>

Enhancement of finish to 150mm walls

42 m3

64 nr

32 m2

10 m3

63 m2

1.31 t

63 m2

166 m2

33 m3

331 m2

3.32 t

331 m2

672 m

4.446 m2

1.327 m3

8.892 m2

165.87 t

8.892 m2


185 m2

28 m3

370 m2

3.49 t

370 m2



### Upper floors

**Element unit quantity: Upper floors**

Total area of upper floors measured as for GIFA

The area measured is the area of the floors related to the frame - elemental cost

7,285 m2

7,285 m2

**Concrete floors** Definition: Reinforced and post tensioned concrete suspended floors  
**Suspended floor slabs** Details, including thickness (mm); concrete strength (N/mm<sup>2</sup>), reinforcement rate (kg/m<sup>3</sup>) and type of formwork finish, to be stated

**Insitu Concrete**

Concrete Slabs to Lower Ground Floor (300mm thick)

C40 concrete to lower ground slab

Soffit formwork to lower ground slab

Reinforcement to lower ground slab (145kg/m<sup>3</sup>)

Worked finish to lower ground

Sundries / Detailing to lower ground

1,054 m2

316 m3

1,054 m2

108.54 t

1,054 m2

1,054 m2

Allowance for forming ramps between gridlines 4 and 9

Allowance for movement joints / crease lines

Concrete Slabs to remaining upper floors (300mm thick)

Concrete (Assumes C40 Mix) upper floors

Formwork upper floors

Reinforcement (145kg/m<sup>3</sup>) upper floors

Worked finish upper floors

Sundries / Detailing

Concrete Roof slab (300mm thick)

Concrete (Assumes C40 Mix) to roof slab

Formwork to roof slab

Reinforcement (145kg/m<sup>3</sup>) to roof slab

Worked finish

Sundries / Detailing

Enhancement of finish to Soffits to all Net Areas - Board / joint layouts only

5 item

4 item

6,230 m2

1,992 m3

6,276 m2

288.78 t

6,230 m2

6,230 m2

49 m2

92 m3

49 m2

13.41 t

49 m2

49 m2

49 m2

7,282 m2



CPE312 BLAVATNIK SCHOOL OF GOVERNMENT - Stage D

A.01 Stage D (25%) Quantification

A.01.2 General Quantification sheet 2

© Laing O'Rourke 2012, all rights reserved - Do not scale from this drawing

© Laing O'Rourke 2012, all rights reserved



## Core 4 – Bid Production Support



- ☒ Inception
- ☒ Concept / optioneering
- ☒ Scheme design
- ☒ Detailed design

**Responsible:**  
**Construction process engineer**

**Consulted:**  
**Bid production**




- Visuals from the model to support bid production
- Authoring of BIM sections of the bid to ensure consistency and full demonstration of our capabilities
- Presentational material can be produced based on model views

1. Example of annotated output used to demonstrate building properties within submission document




# Digital Engineering in Work Winning - where are we now?

Into 4D – the model is exported to the project planner for application of programme.



3D Model + Programme = 4D Programme

## Core 6 – Model Developed to Enable Planning Team 4D



- ☒ Inception
- ☒ Concept / optioneering
- ☒ Scheme design
- ☒ Detailed design

**Responsible:**  
**Planning lead**


**Consulted:**  
**Construction process engineer**

- The planning team can develop the programme in 4D to interrogate and validate the programme sequence and methodology, plus logistics
- The model will be linked to the schedule to an agreed level of detail to facilitate the above
- The bid team can then produce 4D stills and animations from this to support bid presentations and documentation
- Visualise occupational phasing

1	2	3
4	5	6
7	8	9


1-9. Sequence clearly articulated through the use of the 3D model linked to programme and methodology





# Digital Engineering Why?

# The Public Sector Road Map



## Level 0

Unmanaged 2D CAD with paper or uncontrolled electronic exchange

## Level 1

Managed 2D/3D CAD in collaborative environment, using some common data structures. No integration of commercial function

## Level 2


Controlled 3D collaboration with multidiscipline data shared, possibly using 4D, 5D and feeding operational systems

## Level 3

Fully open process and data integration through web based data systems and compliant with IFC/IFD standards To deliver an integrated set of geometric models, data and documentation that builds over a the life of a project to capture all knowledge related to that project



# Potential Impact on LOR UK Work Opportunity due to low Investment




Assumed against a continued flat UK work win volume & 55/45% public/private sector split

Early public sector adopters eg. MOJ Procurement

Public sector Level 2 BIM mandate in place

## Why? – Opportunity...

Government publications are quoting at least 5% saving opportunity, 10% on BAA projects





## Digital Engineering – Capturing Evidence

### Digital Engineering Case Studies

- Project Case Studies written quarterly;
- linked to DE Value Wheel & Deliverables Menu
- Produced at Bid & throughout Project Delivery



- Project Team Member Testimonials
- Case Studies published to iGATE

Post Win BIM Case Study, Ref: 077

BIM Eng: Elliot Mawbey, 13/12/12; Q4 2012  
The Leadenhall Building

#### Design Development / Cost Certainty B09 - Regular Design Production Collaboration Established The Leadenhall Building



**Client:**  
British Land & Oxford Properties  
**Project partners:**  
Rogers Stirk Harbour+Partners  
**Aim:**  
**Value:**  
£200-250m  
**Duration:**  
2011-2013  
**Brief:**  
High rise Commercial Office with  
Ground Floor retail space in the  
City of London

##### Aim

To provide a collaborative forum for reviewing the design information with all stakeholders in a 3D environment prior to commencing manufacture of the major building elements, steelwork, MEP, precast elements and cladding. The objective of these sessions was to achieve a high degree of design assurance prior to progressing to the manufacturing and assembly phases of the project.

##### Results

These collaborative sessions provided a forum for a collective design "sign-off" at key intervals during the design process. This provided the team with greater certainty moving into the delivery phase of the project. It also provided the different disciplines with a greater appreciation of the challenges their team members were faced with, this resulted in a broader understanding and a more collaborative joined up approach to problem resolution.

#### Collaborative Design Reviews - "Design Assurance"

##### Design Assurance

To provide the project team and the client with sufficient certainty to proceed with the approval of design information for manufacture, the Leadenhall Team carried out a number of "Design Assurance" sessions in Laing O'Rourke's Collaboration Suite. Using the combined Master Model the team were able to carry out joint reviews of the design information utilising the model to identify outstanding issues ahead of commencement of manufacture at critical stages.

##### Visual Agenda

The key to successfully utilising the model in the session was creating a visual agenda within the model ahead of the session allowing quick navigation to the areas to be reviewed.

##### Conclusion

These design assurance sessions helped all stakeholders understand the complexities of the building and provided a forum for open discussion. They helped break down the barriers between the different disciplines as all parties had a greater understanding of each other's constraints.

- Achieve design assurance at key stages
- Thorough review of key elements/ interfaces
- Greater certainty achieved moving into the manufacture & assembly phases




"Even the sceptics in the team saw the benefit and wanted more of these sessions!"  
Richard Upsall - Senior Design Manager

© Laing O'Rourke 2012, all rights reserved



## Digital Engineering – Project Overview

- **Project Name**
- Leadenhall Project



Value - £235m

*A landmark job in central London with a highly complex structure. With limited influence on the design Laing O'Rourke have used BIM to resolve co-ordination issues with the design team and supply chain ahead of constructing on site whilst delivering innovative construction techniques, ensuring high level HSE standards on a project that presents a higher proportion of risk due to the nature of the building.*




### Areas of impact

#### Primary

- Design development
- Co-ordination and clash detection

#### Secondary

- Programme and Methodology
- HSE performance
- DfMA
- Reputation
- Quality







# Digital Engineering Setting Up for Success

# The Right Organisation

*Right People*

(appropriately trained\*, with right culture operating in right structure)

Working with the *Right* tools


(technology\* ie hardware / software and supporting infrastructure)

Working in the *Right* way

(our agreed strategy and our business processes\*)


On the *Right* projects

(improved pipeline selection process)






## Deployment of Digital Engineer – towards 2020




# DE Protocols

- **Why are these so fundamentally important?**
  - review capability & capacity of the stakeholders
  - review software and file format for data exchange
  - agree overall model responsibilities
  - agree who is modelling what, to what level of detail and when
  - agree model grid, origin & orientation
  - sets out regular model sharing process
  - sets out specific modelling requirements to support DE Deliverables
- **Need to be agreed at the earliest opportunity**






# BIM Engineer Support



Intensity of BIM Engineer support to drop over time as project teams become able to take on role/responsibility of delivery

# Technology

## Software Interface – ‘typical software’








# Digital Engineering

## Engineering function example

---

## Digital Engineering in Delivery for Engineers

---





---

# Digital Engineering in Delivery - where are we now?

---

## Where are we now?

- Sometimes a Digital Engineer from the office sorts it.
- Some projects have a model, some don't,
- Some consultants provide their model, some don't,
- Pricing & Digital Engineering manage the development and implementation of Digital Engineering along with site based Digital Engineers to ensure consistent approach and processes across the Bu's and focus investment in R&D.

## Where we need to be?

- Delivery teams drive Digital Engineering (Our Digital Engineers support). Engineers are well placed to drive the best from Digital Engineering.
- Our consultants providing the right information in the right format, at the right time. Digital Engineering protocols used to manage this process.
- The Digital Engineering model in delivery is authored by the design teams and managed by Laing O'Rourke.
- The business expects Digital Engineering to be deployed to its optimum across all projects.




Digital Engineering

Tracking Progress / Reporting



# Digital Engineering Implementation Plan



- DE Deliverables form Project Implementation Plan
- deliverables & responsibilities
- revised contract review form
- on-going point of reference



## University of Bath R6 Student Accommodation Digital Engineering Implementation Report

July 2013

Project Title	University of Bath - R6 Student Accommodation	Region	Wales & West	Pre-construction Scores				Construction Scores			
				Planned	50%	Actual	67%	Planned	50%	Actual	67%
Project Status	Pre-construction	Location	Education	End Target	50%	Actual	67%	End Target	50%	Actual	67%
Owner	4 Trust	Report date	10-Jun-13	End Target	50%	Actual	67%	End Target	50%	Actual	67%
Delivery date / status											
Pre-construction delivery data / status											
ref / action	Laing O'Rourke BIM Objectives			planned start	planned end	actual end	status	planned start	planned end	actual end	status
001	BIM Protocol / Level of Delivery established			Feb-2013	May-2013	May-2013	Completed	Feb-2013	May-2013	May-2013	Completed
002	BIM enabled IT Infrastructure / Personal Hardware established			Feb-2013	May-2013	May-2013	In progress	May-2013	Jun-2013	Jun-2013	Completed
003	Managed 3D / BIM Environment established			Feb-2013	May-2013	Jun-2013	In progress	May-2013	Jul-2013	Jul-2013	In progress
004	MSP Modelling Strategy established			Mar-2013	Apr-2013	Apr-2013	Completed	Mar-2013	Apr-2013	Apr-2013	Completed
005	Data Exchange with Owners established utilising modelled data			Feb-2013	Jun-2013	Jun-2013	Completed	Feb-2013	Jun-2013	Jun-2013	Completed
006	Existing Surveys undertaken in 3D format			-	-	-	N/A	-	-	-	N/A
007	Drawings & Schedules Produced from Model			Feb-2013	May-2013	May-2013	Completed	Feb-2013	May-2013	May-2013	Completed
008	Accurate Monthly Reporting of BIM Implementation			Feb-2013	May-2013	May-2013	In progress	May-2013	Jul-2013	Jun-2013	In progress
009	Regular Design / Production Collaboration established			Feb-2013	May-2013	May-2013	In progress	May-2013	Jul-2013	Jun-2013	In progress
010	Regular Design / Production Clash Detection established			Feb-2013	Jun-2013	Jun-2013	Completed	Feb-2013	Jul-2013	Jul-2013	Pending
011	Change reviewed within model to monitor for 'Design to Cost'			-	-	-	-	-	-	-	-
012	Key Design / Production quantity take-off scheduled from model			-	-	-	-	-	-	-	-
013	Model utilised to enhance Tender Package Management			-	-	-	-	-	-	-	-
014	Specific Technical details identified and worked through in 3D			-	-	-	-	May-2013	Jul-2013	Jul-2013	In progress
015	Model utilised for elements of site setting out			Feb-2013	Jun-2013	Jun-2013	Completed	Feb-2013	Jun-2013	Jun-2013	Completed
016	4D model for sequencing & programme validation			Feb-2013	Jun-2013	Jun-2013	Pending	Feb-2013	Jun-2013	Jun-2013	Pending
017	4D model for programme & progress communication			Feb-2013	Jun-2013	Jun-2013	Completed	Feb-2013	Jun-2013	Jun-2013	Completed
018	Site Context, Logistics & Temporary Works Modelled			-	-	-	-	Mar-2013	Jun-2013	Jun-2013	Completed
019	Site Installation Remediation Proposed			-	-	-	N/A	Mar-2013	Jun-2013	Jun-2013	Completed
020	Model utilised to review impact on Health & Safety			-	-	-	-	-	-	-	-
021	Model utilised for End User / Client / Neighbourhood communication			-	-	-	-	-	-	-	-
022	Digital O&M Manual linked to Model for FM			-	-	-	-	-	-	-	-



### Comments & Issues

Pfjggjj jcodjodcj  
 j j ihdihdwq i wdih ihdi dwidhiwdq iwd i  
 Dsjcdjosdijo ds  
 Djcdojc djc ihdihwih i ieh dieihhie ie  
 Cdijcdojcdojc o cdoco ocjcdco c odjcdjcsd  
 odc

## Digital Engineering Implementation Plan

- **DE Deliverables form Project Implementation Plan**
- awareness, training & application engagement
- on-going point of reference

Surname	Forename	Department	BIM Engagement		
			Awareness	Software Trained	Applying
		Project Leader			
		Design Manager			
		Planner			
		Planner			
		Engineer			
		Engineer			
		Engineer			
		Engineer			
		Commercial			
		Construction Manager			

### Legend

(training / application)

Red

in-complete / not applying

Amber

in-part / partial

Green

complete / applying

### Digital Engineer time allocation

100%

100% - 12 months

Reduced level of support

25% - 6 months

10% - as req'd

0%


average allocation  
(example)

## Digital Engineering Reporting

- **DE Implementation Plans form summary reports**
- Project reporting
- Engagement reporting
  - Quarterly update to Functional Leaders
    - Update & Key Issues
    - Feedback for continuous improvement & function / discipline requirements

### Post Win Projects

(28)






# UK: Digital Engineering supported Projects in delivery

(Level of support varies across projects)

Aug 2013

Manchester Town Hall  
Manchester St Peters Sq  
West Cumberland Hospital  
Alder Hey Children's Hospital  
Glan Clwyd  
Oldham College  
Salford BSF Schools  
Beswick Hub  
Stoke CBD  
Chester Zoo  
Victoria Gate Shopping centre

Bristol Royal Infirmary Ward Block  
Bristol Haematology & Oncology Centre  
University of Bath R6  
Llandough AMHU – Cardiff  
Aberdare Community School (Sobell)  
Ysgol Cwm Gwendraeth  
SCCC



RHSC Royal Hospital for Sick Kids  
Ryhope (Pride)  
Monkwearmouth (Pride)  
Monument Mall  
Scottish Power HQ  
Scottish Water (SR10);  
• Forehill & Bothwellbank

Stafford Area Rail Improvement  
A453 Road Widening  
Oxford University Blavatnik

Liverpool Street Station (Crossrail)  
Tottenham Court Road Station (Crossrail)  
Custom House (Crossrail)  
Francis Crick Institute  
Kings Health Partnership @ Guys  
Leadenhall  
WSQ Dagenham Housing  
Heathrow - MSCP CP2  
Clarges Estates  
Elephant Road  
Cambridge Adenbrookes

Brighton 3T's Hospital



# Digital Engineering Project Examples

---

# Salford BSF: Phase 2

BIM (post win) summary by Andy Radley



Salford BSF –	Phase 1:	Walkden High School
		Irlam High School
Salford BSF –	Phase 1b:	The Oasis Academy
Salford BSF –	Phase 2:	St Ambrose RC High School
		St Patricks RC High School
		Moorside Campus

### **St Ambrose RC High School**

Project value: £21.6m

Contract duration: 72 weeks



### **St Patricks RC High School**

Project value: £18.0m

Contract duration: 72 weeks



### **Moorside Campus**

Project value: £32.0m

Contract duration: 81 weeks





### **Project design team**

Architects:	Aedas
Structure & Civil:	Aecom
MEP Design:	Aecom
Landscaping:	Plinke




### **Level of delivery**

Architecture:	3D parametric (building)
Structure:	3D parametric (building)
M&E:	3D parametric (main vertical and horizontal distribution runs)
External works & landscaping	– 2D only



Salford BSF: Phase 2 – Asite Navigator utilised



Salford Phase 2: St Patricks - Model upload and review / comment schedule (prior to each DTM)

Design Team Meeting Day: **Wednesday**


	Monday	Tuesday	Wednesday	Thursday	Friday	Sat	Sun	Monday	Tuesday	Wednesday	Thursday	Friday	Sat	Sun
Main Contractor: LDR			UPLOAD						REVIEW	DTM				
Architect: Aedas			UPLOAD					REVIEW		DTM				
Structural: Ascom			UPLOAD		REVIEW					DTM				
MFP: Aecom			UPLOAD	REVIEW						DTM				
Crown House			UPLOAD	REVIEW						DTM				
Other:			UPLOAD							DTM				
Other:			UPLOAD							DTM				
Other:			UPLOAD							DTM				
Other:			UPLOAD							DTM				
Other:			UPLOAD							DTM				
Other:			UPLOAD							DTM				

NOTE: The date of the Design Team meetings is to be co-ordinated by the Design Manager

**UPLOAD:** This refers to the day each consultant who produces a model file publish it to Asite in their relevant folder under 'BIM Live Data' and is to be captured as a work in progress.



**REVIEW:** This refers to day allocated to a consultant access the combined model file (TeamWorks) and comment as required. Access to the combined model is to be through the use of Asite Navigator.

NOTE:  
The combined model file will be created and published to Asite online Asite Navigator by the project BIM Engineer. All team members to this schedule and the use of Asite Navigator is to be directed to the project BIM Engineer.  
The use of Asite Navigator is essential to maintain a working live BIM model environment and to manage to converging process. This process is to be managed by the project Design Manager with support by the BIM Engineer.







## Salford BSF: Phase 2 – Structure co-ordination




Cost to project: £2,000 and 3 day delay in programme for redesign and rectification works

## Salford BSF: Phase 2 – Structure co-ordination








## Salford BSF: Phase 2 – Structure co-ordination with DfMA products




Cost to project: £1,000, 1 day delay in programme, and additional H&S risk for redesign and rectification works





1. AECOM M&E base Revit model
2. CHt developed AECOM model to produce a production Revit model
3. Exported to CADMEP+ for module manufacture


## Salford BSF: Phase 2 – MEP Penetrations modelled & co-ordinated






## Salford BSF: Phase 2 – Data exchange with EIP

### Consultants Revit design model



### Explore's Nemetschek production model




Design to Manufacture



Salford BSF: Phase 2 – Construction method statements


Standard Structures - 5) Ambience  
 Scaffold and Wagon Frame 2  
 Pressed Ground Beam  
 APB\_H0\_005

3.4 Reinforcement




Step 3.5 Place cap links

Take opposing beam joggled reinforcement bars and place the remaining pile cap links in position but do not fix.




Step 3.6 Beam top steel


Place in the beam top reinforcement but do not fix.



Step 3.7 Pile cap top mat installation


Take in the remaining pile cap top reinforcement and position the previously placed pile cap links.








Salford BSF: Phase 2 – Logistics modelled & used within site induction




Rory O'Donoghue: Construction Manager  
..."It worked really well, and I would definitely use it again..."



## Salford BSF: Phase 2 – Automated pile co-ordinate creation & extraction




PILE REF.	PILE DIAMETER	EASTING - X	NORTHING - Y	PILE LOAD (kN) SLS	PILE CUT OFF LEVEL (m)
P01	600mm	376267420.668772	402732566.884223	850	87.895
P02	600mm	376270048.016092	402734588.899267	625	87.955
P03	600mm	376272267.524597	402737113.815381	750	87.745
P04	600mm	376273202.317357	402735925.053754	750	87.745
P05	600mm	376275302.223493	402738631.900596	500	87.955
P06	600mm	376277541.885633	402741157.152452	675	87.745
P07	600mm	376279456.668070	402735868.302733	675	87.745
P08	600mm	376280167.137154	402742390.938665	725	87.955
P09	600mm	376282444.870844	402744120.311096	750	87.895
P10	600mm	376285535.587373	402746506.715480	700	87.955
P11	600mm	376288616.804314	402746877.737936	700	87.895
P12	600mm	376291053.477263	402750752.807420	600	87.955
P13	600mm	376293467.340848	402752610.284844	675	87.895
P14	600mm	376295999.862843	402754559.112503	575	88.045
P15	600mm	376298061.310128	402756130.520086	650	87.895
P16	600mm	376300489.132705	402758019.465173	500	87.895
P17	600mm	376271634.716788	402725860.870701	875	87.675
P18	600mm	376277673.486502	402776775.657949	875	87.675




**excitech**  
technology for design

# St Ambrose Barlow RC Project 4D Position Review


## DABS 8.05.12 Objectives for the Week



St Ambrose Barlow RC Project 4D Position Review  
DABS Safety Awareness Hazards for the Week




St Ambrose Barlow RC Project 4D Position Review  
DABS Safety Awareness Areas for the Week




Chris Buckley: Expanded Project Manager  
**...”When you get the lads on site asking for the 3D visual you know its working...”**

WC 16<sup>th</sup> July 2012 – Objectives for the Week  
Construction Zone A & B



- 1<sup>st</sup> Side Boarding In Progress
- 1<sup>st</sup> Side Boarding Complete
- M&E Drops & Patresses To Progress
- M&E Drops & Patresses Signed Off

Action	Owner	Target Date
M&E Patresses Marked Out	Rory O'D / G Sullivan	20.07.12
Conduit / Containment Electrical Drops in Walls	James Thrall, Gary Sullivan	20.07.12
Builders Works Patresses Marked Out	Rory O'Donoghue	20.07.12
Patresses Installed	Jock Nugent / Rory O'Donoghue	20.07.12
Sign Off Walls for 2 <sup>nd</sup> Side	LOR, CHT & Jock Nugent	20.07.12




St Ambrose Weekly Planning Progress & Objectives W/c 16.07.12

Ground floor





WC 16<sup>th</sup> July 2012 – Objectives for the Week  
Construction Zone D





- 1<sup>st</sup> Side Boarding In Progress
- 1<sup>st</sup> Side Boarding Complete
- M&E Drops & Patresses To Progress
- M&E Drops & Patresses Signed Off

Action	Owner	Target Date
Corridor Boarding High Level Both Sides	Rory O'D / J Nugent	20.07.12
1 <sup>st</sup> Side Boarding	Rory O'D / J Nugent	20.07.12
M&E Corridor Modules	Gary Sullivan	20.07.12



St Ambrose Barlow RC – Asphalt Package  
Programme – Sub Contract Work Areas






1. Fire protected steelwork highlighted
2. Images and Model sent with a link to Navisworks Freedom to external contractor to support package scope of works



## **Lessons learnt for next project**

- BIM integration being part of consultant appointment
- Specifically selected external design team members
- Improve understanding of LOR message to functions – people are unaware
- Early Project engagement and appointment of objective leads
- Promote greater design stage collaboration and clash detection



© Laing O' Rourke 2012, all rights reserved.

No part of this presentation may be reproduced, stored on a retrieval system, disclosed or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without prior permission of the copyright owner.

LAING O'ROURKE